## Miscellaneous (II part) 2018-19

## Related Infrastuture works :-

1	Vitrified tiles –providing and fixing vitrified tiles size (24"x24")complete with cutting and filing joints with cements	Square meter
2	Kata Stone- Providing and Fixing Kota Stone Size 22"x22" Complete with cutting and filling joint with white cement. (For roof) (Standard Quality)	Sq.mtr.
4	False Celling- Providing and Fixing False Celling with GIT channels with Steel Expansion Fastners and Accoustical Celling Tiles (Make Saint-Gobain/Arm Storng)	Sq. ft
6	Aluminium Pennell (Partition)- Providing and fixing aluminium Pennell with aluminium section 2.5"xl.S" (Aproximate) with 6mm Glass or 12 mm both side laminated board (Openable)	Sq ft
7	Aluminium Window- Providing and fixing aluminium Window with aluminium section frame 2.5"x1.5" thikness 1.5mm 2track sliding window with Smm glass with handle and lock.	Sq ft
8	Aluminium Door- Providing and fixing aluminium door with aluminium section 3"x 1.3/4" thikness 2mm with 6mm glass and 12mm both side laminated board.	Sq ft
10	Hydrolic Door Closer- Providing and fixing Hydrolic Door Closer (Make Standard Quality)	Sq ft
12	Bathroom Fittings- (a) Commode- Commode with commode cover, cistern with PVC fittings (Make Parryware / Hindware)	Per unit
	(b) Wash basin- Wash basin with PVC fitting fittings (Make Parryware I Hindware), Squire Jaquar (Ark)	Per unit
	(c) Angle Cock (Make Parryware I Hindware), Squire Jaquar (Ark)	Per unit
	(d) Pillar Cock (Make Parryware / Hindware), Squire Jaquar (Ark)	Per unit
	(e) Glass with soap Stands (Make Parryware I Hindware), Squire Jaquar (Ark)	Per unit
	(f) Towel Hanger (Make Parryware I Hindware), Squire Jaquar (Ark)	Per unit
	(g) Mens/Womens urinal- Mens urinal with all PVC fitting Hanger (Make Parryware I Hindware), Squire Jaquar (Ark)Hindware)	per unit

