

PG Infrastructure work

(2018-19).

Code No.	Item	Unit
1. 8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. : Area of slab over 0.50 sqm	sqm
2. 8.9.1.2	Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and cement slurry @ 3.3 kg/ sqm including pointing in white cement complete. : Granite of any colour and shade	sqm

[Handwritten Signature]
10/5/18